


BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

CLEARING AND GRUBBING
TO SERVE CRESCENT CAMPUS BOULEVARD
CONROE MUNICIPAL MANAGEMENT DISTRICT NO. 1
CITY OF CONROE, MONTGOMERY COUNTY, TEXAS
JANUARY 4, 2018
LJA ENGINEERING, INC.
P.CHATTERJEE
JANUARY 5, 2018
2274-1706A (9.2)

BIDDER'S NAME	TOTAL BID AMOUNT
1) CROSTEX CONSTRUCTION, INC.	\$110,400.00
2) DOUBLE OAK CONSTRUCTION, INC.	\$122,352.00
3) SONORA SWQM CO. DBA SONOTA CONST.	\$155,410.00

CALENDAR DAYS - 30/45



Edmund D. Rucker

I, Edmund D. Rucker, P.E., hereby certify these bid tabulations to be true and correct.

BID TABULATION FOR:

BID OPENING DATE:
BID OPENING LOCATION:
TABULATION BY:
TABULATION DATE:
LJA JOB NO.

**CLEARING AND GRUBBING
 TO SERVE CRESCENT CAMPUS BOULEVARD
 CONROE MUNICIPAL MANAGEMENT DISTRICT NO. 1
 CITY OF CONROE, MONTGOMERY COUNTY, TEXAS
 JANUARY 4, 2018
 LJA ENGINEERING, INC.
 P.CHATTERJEE
 JANUARY 5, 2018
 2274-1706A (9.2)**

ITEM DESCRIPTION	UNIT	QTY	1) CROSTEX CONSTRUCTION, INC.		2) DOUBLE OAK CONSTRUCTION, INC.		3) SONORA SWQM CO. DBA SONOTA CONST.	
			UNIT COST	TOTAL COST	UNIT COST	TOTAL COST	UNIT COST	TOTAL COST
CLEARING AND GRUBBING ITEMS								
1. CLEARING AND GRUBBING OF ROAD RIGHT-OF-WAY, COMPLETE IN PLACE	AC	10.7	\$4,500.00	\$48,150.00	\$2,700.00	\$28,890.00	\$5,000.00	\$53,500.00
2. CHIPPING AND HAULING OFFSITE OF CLEARED ROAD RIGHT-OF-WAY MATERIAL, COMPLETE IN PLACE	AC	10.7	\$1,000.00	\$10,700.00	\$3,280.00	\$35,096.00	\$3,800.00	\$40,660.00
3. REMOVE EXISTING GRAVEL ROAD, INCLUDES DISPOSAL OF ANY MATERIALS OFF SITE, COMPLETE IN PLACE	SY	520	\$10.00	\$5,200.00	\$20.00	\$10,400.00	\$2.00	\$1,040.00
4. CLEARING AND GRUBBING OF PRIVATE UTILITY EASEMENTS, COMPLETE IN PLACE	AC	3.1	\$4,500.00	\$13,950.00	\$2,700.00	\$8,370.00	\$5,000.00	\$15,500.00
5. CHIPPING AND HAULING OFFSITE OF CLEARED PRIVATE UTILITY EASEMENTS, COMPLETE IN PLACE	AC	3.1	\$1,000.00	\$3,100.00	\$3,280.00	\$10,168.00	\$3,800.00	\$11,780.00
6. CLEARING AND GRUBBING OF AREA BEYOND R.O.W. FOR GRADING PURPOSES, COMPLETE IN PLACE	AC	0.2	\$4,500.00	\$900.00	\$2,700.00	\$540.00	\$5,000.00	\$1,000.00
7. CHIPPING AND HAULING OFFSITE OF AREA BEYOND R.O.W. FOR GRADING PURPOSES, COMPLETE IN PLACE	AC	0.2	\$1,000.00	\$200.00	\$3,280.00	\$656.00	\$3,800.00	\$760.00
8. CLEARING AND GRUBBING DEMUCK, SCARIFY OF EXISTING LOW AREAS, COMPLETE IN PLACE	AC	1.25	\$5,000.00	\$6,250.00	\$3,900.00	\$4,875.00	\$5,000.00	\$6,250.00
9. CHIPPING AND HAULING OFFSITE OF LOW AREAS MATERIAL, COMPLETE IN PLACE	AC	1.25	\$1,000.00	\$1,250.00	\$3,280.00	\$4,100.00	\$3,800.00	\$4,750.00
10. ORANGE CONSTRUCTION FENCING FOR WATERS OF THE UNITED STATES, 4' HEIGHT WITH 10' MAXIMUM POST SPACING, AS DIRECTED BY THE ENGINEER, COMPLETE IN PLACE	LF	730	\$3.00	\$2,190.00	\$1.50	\$1,095.00	\$5.00	\$3,650.00
11. ADDITIONAL CLEARING AND GRUBBING AND HAULING OFFSITE OF CLEARED MATERIAL AS NECESSARY FOR ACCESS TO SITE (TO BE PERFORMED ONLY AT THE DIRECTION OF THE ENGINEER), COMPLETE IN PLACE	AC	1	\$5,500.00	\$5,500.00	\$2,700.00	\$2,700.00	\$6,000.00	\$6,000.00
SUBTOTAL CLEARING AND GRUBBING ITEMS				\$97,390.00		\$106,890.00		\$144,890.00
MISCELLANEOUS ITEMS								
1. STABILIZED CONSTRUCTION EXIT, COMPLETE IN PLACE	EA	3	\$1,500.00	\$4,500.00	\$3,000.00	\$9,000.00	\$1,800.00	\$5,400.00
2. REINFORCED FILTER FABRIC FENCE, COMPLETE IN PLACE	LF	4,520	\$1.75	\$7,910.00	\$1.35	\$6,102.00	\$1.00	\$4,520.00
3. INLET PROTECTION BARRIER, COMPLETE IN PLACE	EA	6	\$100.00	\$600.00	\$60.00	\$360.00	\$100.00	\$600.00
SUBTOTAL MISCELLANEOUS ITEMS				\$13,010.00		\$15,462.00		\$10,520.00
BID SUMMARY								
SUBTOTAL CLEARING AND GRUBBING ITEMS				\$97,390.00		\$106,890.00		\$144,890.00
SUBTOTAL MISCELLANEOUS ITEMS				\$13,010.00		\$15,462.00		\$10,520.00
TOTAL AMOUNT BID				\$110,400.00		\$122,352.00		\$155,410.00